

installation & maintenance

CONDENSING UNITS CUS 15 - 60/HCU 20 - 30D



About Airedale

WARRANTY, COMMISSIONING & MAINTENANCE	Our standard warranty package guarantees all parts for 24 months. Additional customised warranty packages are also available for periods of 12 to 36 months covering either parts only or parts and labour.						
	Having chosen your Airedale product, a full commissioning service is now available on all products and is charged on a daily rate variable by location.						
	To further protect your investment in Airedale products, we have also introduced our own Planned Maintenance Service. This includes nation-wide service cover 24 hours a day, 365 days a year, plus regular planned maintenance visits. For a free quotation contact our Field Service Department or your Local Sales Engineer.						
TRAINING	As well as our comprehensive range or Refrigeration and Air Conditioning Trais contact our Training Co-ordinator.	well as our comprehensive range of products, Airedale offers a modular range of rigeration and Air Conditioning Training courses, for further information please tact our Training Co-ordinator.					
CUSTOMER SERVICES	For further assistance, please e-mail: enqu	iries @airedale.com or tele	ephone:				
	UK Sales Enquiries International Enquiries Spares Hot Line Airedale Service Technical Support Training Enquiries	es + 44 (0) 113 238 7789 uk.sales @airedale.c uiries + 44 (0) 113 239 1000 enquiries @airedale.co + 44 (0) 113 238 7878 spares @airedale.co + 44 (0) 113 239 1000 service @airedale.co + 44 (0) 113 239 1000 service @airedale.co + 44 (0) 113 239 1000 service @airedale.co * 44 (0) 113 239 1000 marketing @airedale.co					
	For information, visit us at our Web Site: w	ww.airedale.com					
	AIAC Ltd endeavours to ensure that th fairly stated, but none of the statement representation of fact. AIAC Ltd does for any reliance placed on the informat	urs to ensure that the information in this document is correct and one of the statements are to be relied upon as a statement or act. AIAC Ltd does not accept liability for any error or omission, or uced on the information contained in this document.					
	The development of Airedale products in this document may not be up to date with AIAC Ltd at the address stated. T unless expressly agreed.	e development of Airedale products and services is continuous and the information his document may not be up to date. It is important to check the current position h AIAC Ltd at the address stated. This document is not part of a contract or licence ess expressly agreed.					
	No part of this document may be repro- means, electronic or mechanical, inclu- storage and retrieval systems, for any use, without the express written permis	t of this document may be reproduced or transmitted in any form or by any , electronic or mechanical, including photocopying, recording, or information and retrieval systems, for any purpose other than the purchaser's personal thout the express written permission of AIAC Ltd.					
	© 2014 Airedale International Air Cond Printed in the UK.	ditioning Limited. All righ	nts reserved.				

Description	Page 4
General Safety Spares Serial Plate	Page 5 Page 5 Page 5
Warranty Main Terms Procedures Returns Analysis	Page 6 Page 6 Page 7
Loose Items List	Page 7
Component Location / Description	Page 8
Site Installation Guide	Page 9
Mechanical Information Technical Data Sheet	Page 10
Dimensions	Page 11
Refrigeration System Refrigeration Pipework Schematics System Holding Charge Pipework Sizing / Oil Addition Pressure Testing Evacuation Refrigerants	Page 14 Page 15 Page 15 Page 15 Page 15 Page 15
Electrical Information Electrical information - Control panel components Electrical Data Sheet Terminal Blocks - External Connections	Page 16 Page 17 Page 18
Commissioning Procedures Commissioning Sheet - Example Pre-Start Checks Refrigeration Circuits - Charging Head Pressure Controller Adjustment	Page 19 Page 20 Page 20 Page 20
Troubleshooting Tables	Page 22
Maintenance Requirements Periodic Maintenance Schedule	Page 25

Description INTRODUCTION	The condensing units comprise a compact housing incorporating all the necessary components and associated controls required. The multiple condenser fan and motor assemblies provide an even airflow across the condenser coils and then discharge vertically upwards. The condenser coils are in a "V" formation on units in the range CUS 15 to 30D and in a twin vertical formation on units in the range CUS 40 to 60D and HCU 20 to 30D.								
COMPRESSORS	CUS 15 - 30D AND HCU 20 - 30D								
	Three phase hermetic scroll compressors are used in this range of condensing units. They are fitted with an internal thermal protector to protect the compressor from damage against high motor winding and discharge gas temperatures.								
	CUS 40 - 60D								
	Three phase fully hermetic twin scroll compressors are used enabling each of the two circuits to operate at 50% or 100% duty according to demand. Each twin compressor is fitted with a thermistor protector module to protect the compressor from an overheat condition.								
REFRIGERATION	Each circuit is fitted with a liquid line shut-off valve to allow for isolation of the condensing unit during service or maintenance, and this is fitted with a schraeder access connector to facilitate connection of a service gauge manifold.								
	The suction line connection is capped and sealed ready for customer connection.								
	A large capacity filter drier is supplied loose for on-site installation.								
	A manual high pressure and automatic low pressure cut-out switch is fitted on eac circuit for system safety.								
	All units are configured to operate without pump-down.								
CONTROL PANEL	The control panel is equipped with the necessary MCB's, contactors and other items to provide fully automatic safe operation. It is divided into mains and control sections thereby ensuring voltage integrity between mains (400/230V) and controls (24V).								
OPTIONS	 When specified, the condenser fan is electronically speed controlled to ensure that a stable head pressure can be achieved during all seasons. 								
	2. A weatherproof mains isolator can be fitted to ensure mains isolation of the electrical panel during adjustment and maintenance.								
	3. A soft start option may be fitted to compressors on the CUS 15 to 25D range. This consists of a resistor bank which is inserted in the compressor circuit for 0.3 of a second to reduce current inrush.								
	4. In atmospheres where high corrosion is anticipated phenolic coated aluminium finned coils can be supplied.								
	 A large open mesh coil protection guard can be supplied for sites where coil damage might be a problem (HCU20-30D only). 								
	Compressors can be supplied charged with Ester oil suitable for use with the environmentally friendly refrigerant R407C.								

Conoral Statement

IMPORTANT	The information contained in this manual is critical to the correct operation and maintenance of the unit and should be read by all persons responsible for the installation, commissioning and maintenance of this Airedale equipment.							
SAFETY	The equipment has been designed and manufactured to meet international safety standards but, like any mechanical/electrical equipment, care must be taken if you are to obtain the best results.							
	1	Service and mainte by skilled personne	ould only be carried out					
	2	When working with isolator is switched power to any part o	any air conditio off prior to serv f the equipment	oning units ensure icing or repair wo t.	that the electrical rk and that there is no			
	he unit such as fire alarm							
	4 Electrical installation, commissioning and maintenance work on th equipment should be undertaken by competent and trained perso accordance with local relevant standards and codes of practice.							
	5 Refrigerant No 22 and 407C used in this range of products is classified u the COSHH regulations as an irritant, with set Occupational Exposure Le (OEL) for consideration if this plant is installed in confined or poorly venti areas.							
	6	A full hazard data s should this be requ	heet in accorda ired.	nce with COSHH	regulations is available			
SPARES	A recom the unit. your Co manufae An area recorde	mended spares list For ease of identifi ndensing unit, pleas cture. This informati has been provided o d.	is included in th cation when ord e quote the unit on can be found on the front cove	e unit documenta lering spares or co type, unit serial r d on the serial pla er of this manual f	tion pouch located inside ontacting Airedale about number and the date of te attached to the unit. for this information to be			
SERIAL PLATE EXAMPLE	Airedale Air Cond	REDALE International itioning Ltd.	UK OFFICE Tel: 00 44 113 Fax: 00 44 113	239 1000 250 7219				
	UNIT/GEF SERIAL/S MANUFAC SUPPLY/S FUSE/HAN REFRIGE KÄLTEMIT REFRIGE TEST PRE DRUCKPF PRESSIO DEUTSCH TEL : 00 4 FAX : 00 4	XÄT/UNITE ERIE/SERIE CTURED/HERGESTELLT/ SPANNUNG/ALIMENTATI JPTSICHERUNG/FUSIBL RANT & CHARGE ITTEL & LADUNG RANT & CHARGE ESSURE RÜFUNG N D'ESSAI HES BÜRO 9 6108 90040 9 6108 77972	FABRIQUE ON ES BUREAU FRANCA TEL : 00 331 34 653 FAX : 00 331 334 65	CUS10HI U60179 4/11/98 400V 3PH 50Hz 40.0 A R407C 20.0 BAR IS 3344 53088				
				V ((

Warranty							
IMPORTANT	For the warranty to be valid, copies of the relevant commissioning sheets must be fully completed and returned to Airedale, Leeds, within 28 days of commissioning the equipment. Failure to submit the commissioning sheets within the specified time period will invalidate any future warranty claims.						
MAIN TERMS	The following warranty conditions are subject to the Airedale equipment being regularly serviced and maintained in accordance with the installation and maintenance documents by a competent and qualified installation and maintenance company, approved by Airedale during the warranty period.						
	Airedale will respect warranty cover on all component parts for a period of 24 months commencing from despatch of equipment from the Airedale factory. Extended warranty to afford 24 months cover from commissioning of plant can be supplied upon written request.						
	Airedale warranty cover is appropriate to component parts only and does not include any allowance for labour costs or other expenses involved in the replacement of faulty parts, within the warranty period.						
	Replaced faulty parts should be returned to Airedale within 21 days for full evaluation.						
	Parts fitted under warranty shall be warranted for the unexpired period of warranty of the equipment or 3 months from delivery whichever period is the longer. This excludes compressors on which a further 12 months warranty is granted.						
PROCEDURE	When a component part fails, a replacement part should be obtained through our Spares department. If the part is considered to be under warranty, the following details are required to process this requirement.						
	 Full description of part required, including Airedale's part number, if known. The original equipment serial (U) number. An appropriate purchase order number. 						
	A spares order will be raised under our "G" number system and the replacement part will be despatched, usually within 24 hours.						
	When replaced, the faulty part must be returned to Airedale with a suitably completed and securely attached "Faulty Component Return" (FCR) tag, supplied with each component. FCR tags are available from Airedale Spares Department and supplied with each "G" order.						
	On receipt of the faulty part, suitably tagged, Airedale will pass it to its Warranty department, where it will be fully inspected and tested in order to identify the reason for failure, identifying at the same time whether warranty is justified or not.						
	On completion of the investigation of the returned part, a fully "Report on Goods Returned" will be issued. On occasion the release of this complete report may be delayed as component manufacturer becomes involved in the investigation.						

Warranty PROCEDURE	When warranty is allowed, a credit against the "G" number invoice will be raised. Should warranty be refused the "G" number invoice becomes payable on normal terms.					
	Warranty may be refused for the following reasons:					
	Misapplication of product or components.					
	Replaced part being returned damaged without explanation.					
	Unnecessary delays incurred in return of defective component.					
RETURNS ANALYSIS	All faulty components returned under warranty are analysed on a monthly basis as a means of verifying component and product reliability as well as supplier performance. It is important that all component failures are reported correctly.					
Loose Items List						
FILTER DRIER	A suitably sized liquid line filter drier is shipped loose in the refrigeration compartment of the condensing unit. This has been chosen to match the required refrigeration duty					

panel end by undoing the catches and lifting off.

of the compressor. To access this item, remove the service cover at the electrical

HCU 20 - 30D

operated lockable covers.

Component Location COMPRESSORS HCU 2

	CUS 15 - 30D				
	The compressors are housed in the enclosed compartment which is at one end of the condensing unit and accessible by a series of key operated lockable covers.				
	CUS 40 - 60D				
	The compressors are housed between the condenser coils and are accessible via lockable access covers located at the opposite end of the unit from the control panel.				
CONTROL PANEL	HCU 20 - 30D				
	This is mounted at one end of the unit. It contains all the necessary breakers, contactors and terminals required to operate the unit.				
	CUS 15 - 30D				
	This is mounted above the compressor in the same compartment. It carries all the necessary breakers, contactors and terminals required to operate the unit				
	CUS 40 - 60D				
	This is mounted in the enclosed end of the unit. It carries all the necessary breakers, contactors and terminals required to operate the unit.				
CONDENSER FAN AND MOTOR UNITS	These are integral fan / motor units and are mounted so as to give a vertical discharge of air from the condensing units.				
COMPRESSOR ANTI- CYCLE TIMERS (STANDARD FITMENT)	These are fitted on the control panel and wired in to the control system. It is normally recommended that this be set to a ten minute interval.				
HEAD PRESSURE	CUS 15 - 30D AND HCU 20 – 30D				
CONTROLLER (WHEN FITTED)	This fan speed controller is a single controller with the two sensors connected to it. It operates to sense both circuits at the same time and will sense whichever circuit has a head pressure that is requiring controlling and will vary the fan speeds accordingly.				
	CUS 40 - 60D				
	A separate fan speed controller is fitted to each circuit and will vary the fan speeds for each circuit accordingly.				

The compressors are located in the centre of the unit and are accessed by key

Site Installation Guide

LIFTING	Whenever a condensing unit is lifted, lifting should be from the base. Where possible, all packing and protection should be left in position. If any type of slinging is used, due care should be taken to ensure that the slings do not crush the casework or coil.
	Spreader bars shall be used to ensure that any slings or chains used in the lifting process do not crush the framework of the unit or damage the coil faces.
	Due note shall also be made of the fact that the compressor is at one end of the unit, and therefore the centre of gravity will also be towards that end.
	If the unit is dropped, it shall immediately be checked for damage.
POSITIONING AND LEVELLING	The condensing unit shall be positioned on a stable load bearing and even base. This base shall be levelled to ensure that the compressor operates correctly without uneven internal stresses being transmitted to the compressor support.

Mechanical Information

CUS 15 - 60D

CUS		15D	20D	25D	30D	40D	50D	60D
Nominal Capacity	kW	41.8	50.2	71.1	80.7	104.0	131.4	161.4
Nominal Airflow	m³/sec	4.00	4.80	6.80	6.80	9.60	13.60	13.00
Max.Fan Speed	rpm	930	930	930	930	930	930	930
Refrigerant		R407C						
Refrigerant Charge/Circ	kg	6.5	9.0	9.0	9.0	10.5	10.5	11.8
Oil Charge	Ī	4.0	4.0	4.0	6.6	9.9	9.9	9.9
Liquid Line Connection	ins	5/8	5/8	5/8	5/8	1 1/8	1 1/8	1 1/8
Suction Line Connection	ins	1 1/8	1 1/8	1 1/8	1 3/8	1 5/8	2 1/8	2 1/8
Machine Weight	Kg	440	540	550	695	978	1119	1356

Notes:

- 1 Based on 5°C evaporating and a 30°C ambient.
- 2 Refrigeration charge is for information purposes only. The units do not leave the factory charged.

3 All terminations are suitable for sweat connections.

HCU 20 - 30D

HCU		20D	25D	30D
Nominal Capacity	kW	58.6	69.5	81.0
Nominal Airflow	m³/sec	6.80	6.80	6.80
Max. Fan Speed	rpm	930	930	930
Refrigerant	-	R407C	R407C	R407C
Refrigerant Charge/Circ	kg	10.1	10.3	10.5
Oil Charge	Ī	4.0	4.0	6.6
Suction Line Connection	ins	1 1/8	1 1/8	1 3/8
Liquid Line Connection	ins	5/8	5/8	5/8

Notes:

1 Based on 5°C evaporating and a 35°C ambient

2 Refrigeration charge is for information purposes only. The units do not leave the factory charged.

3 All terminations are suitable for sweat connections.

Dimensions: CUS 15D - 30D



		Α	В	С	D	Е	F	G	Н
CUS 15D	mm	1438	2300	1100	200	-	-	25	1050
CUS 20D	mm	1438	2900	1100	200	1250	1250	25	1050
CUS 25D	mm	1438	2900	1100	200	1250	1250	25	1050
CUS 30D	mm	1438	3000	1100	200	1300	1300	25	1050

		Point Loadings (kg)					Centre of G	ravity (mm)
	A1	B1	C1	D1	E1	F1	Y	Z
CUS 15D	146	-	101	101	-	156	1330	560
CUS 20D	130	120	56	56	121	140	1770	560
CUS 25D	130	122	57	57	123	141	1765	560
CUS 30D	174	140	78	77	138	179	1785	550

Notes:

1 Suction and liquid connections terminate underneath the condenser coil.

2 Allow 500mm around the unit for airflow and maintenance clearance.

Dimensions: CUS 40D - 60D



		Ро	int Loadi	ngs (kg)			Centre of Gra	avity (mm)
	A1	B1	C1	D1	E1	F1	Y	Z
CUS 40D	148	174	174	174	174	149	1169	896
CUS 50D	157	206	206	208	206	156	1136	900
CUS 60D	180	254	254	258	255	180	1116	900

Note: Allow 500mm around the unit for airflow and maintenance clearance.

Dimensions: HCU 20 - 30D



нсц		۸	B	<u> </u>	П	F	F	G
1100		A	D	0	D			0
20D	mm	1993	2280	805	30	2370	150	505
25D	mm	1993	2280	805	30	2370	150	505
30D	mm	1993	2280	805	30	2370	150	505

	Point Loadings (kg)			Centre of Gravity (m		
НСО	A1	B1	C1	D1	Y	Z
20D	140	157	139	131	1088	391
25D	140	157	139	131	1088	390
30D	186.2	206.7	155.7	151.4	1098	372

Suction and liquid connections terminate on the opposite side of the unit to the condenser coil face. 1

2 Allow 1000mm clearance on the coil side for airflow and 500mm clearance on the 3 other sides for maintenance

Refrigeration System

REFRIGERATION PIPEWORK SCHEMATICS



Notes:

- 1 Compressor connections are diagrammatic only not actual.
- 2 For clarity only one circuit is shown although all units are twin circuit.

Refrigeration System

HOLDING CHARGE	All units are shipped with a holding charge of dry nitrogen. This is to ensure that there is no risk of internal contamination or moisture entering the units during shipping or storage.			
	Before the units are evacuated prior to the charging process, the condensing unit should be checked to see that the holding charge has been retained. If it appears to be either partially or totally lost, then the unit concerned should be carefully checked for signs of physical damage.			
PIPEWORK SIZING/OIL ADDITION.	It is MOST IMPORTANT that the correct size refrigeration pipework is used to ensure that the pressure drop in the system is kept to a minimum, and also so that proper oil return will take place under all normal operating conditions.			
	Accepted Good Practice should be followed in the design and installation of the refrigeration pipework system.			
	Oil should be added to the pipework installation in accordance with the compressor manufacturers recommendations where applicable.			
PRESSURE TESTING	When installation is complete, fill the system with dry nitrogen to a pressure of 17 bar/250 psig. Record the pressure over a period of time (a minimum period of 60 minutes should be sufficient to detect any major leaks, however, ideally 24 hours should be allowed). If there is any reduction in pressure, trace the leak and repair before conducting a further pressure test.			
EVACUATION	Evacuation should be carried out with a high vacuum pump. The pump should be connected to the high and low pressure sides of the system via a gauge manifold fitted with compound gauges. A high vacuum gauge should be fitted to the system at the furthest point from the vacuum pump.			
	Triple evacuation should be used to ensure that all contaminants are removed or at least reduced to significantly low proportions. There are no hard and fast rules when applying this method. However, the following has proved effective for general installation and service work.			
	 Recover system charge and pressure test. Replace filter drier. Evacuate to (10 Torr) 13 mBar and maintain for 20 minutes. Break vacuum with OXYGEN FREE dry nitrogen to 0.5 Bar (7psi) and hold for 15 			
	 Evacuate to (5 Torr) 7mBar and maintain for 20 minutes. Break vacuum with OXYGEN FREE dry nitrogen to 0.5 Bar (7psi) and hold for 15 minutes. 			
	 7. Evacuate to (½ Torr) 0.65 mBar and maintain for 1 hour. 7. Evacuate to (½ Torr) 0.65 mBar and maintain for 1 hour. 7. The plant should now be sufficiently dehydrated and suitable for recharging. Note: During installation keep all pipes capped to prevent dirt and moisture ingress. If polyolester oil becomes contaminated with moisture then it is advisable to change the oil and filter drier. 			
ALTERNATIVE REFRIGERANTS	There are now an increasing number of transitional refrigerants as well as the traditional ones and if any refrigerant other than R 22 is used care must be taken in all aspects of installation and charging.			
	This is especially important with regard to the type of compressor oil used, and care must be taken to ensure that the correct oil is used with the correct refrigerant.			
	IMPORTANT:- If an alternative refrigerant is used, then this must be with the approval of Airedale International Air Conditioning Ltd. Use of an alternative refrigerant without the approval of AIAC Ltd could invalidate the warranty.			

Electrical Information

CONTROL PANEL

Standard WiringTheDiagramandsup	condensing units are designed to operate in conjunction with other Airedale units, are also suitable for matching to other air handling units. A wiring diagram is plied with each unit and should be referred to when carrying out the installation.
---------------------------------	---

Components

CUS 15 - 30D AND HCU 20 - 30D

The following MCB's are fitted as standard:

- Single phase control circuit breakers (mains and control voltage). 1
- 2 Three phase compressor circuit breakers.

The following contactors/overloads are fitted:

CP1 and CP2 - Main compressor contactors. 1

- Compressor thermal overload (CU 30D only). 2
- 3 CD1 - Condenser Fan Contactor.
- The following relays are fitted, some are option dependent:
- 1
- R1 Delay Start Relay Circuit No 1. R2 Delay Start Relay Circuit No 2. 2
- R3 HP/LP Trip Relay Circuit No 2 3
- R4 Relay Circuit No 1. 4
- R5 Relay Circuit No 2. 5
- 6 R6 - HP/LP Trip Relay - Circuit No 1

Other components are as follows, some are option dependent:

- **Compressor Sequence Switch**
- 2 T1 - Delay Start Timer - Circuit No 1
- T2 Delay Start Timer Circuit No 2 3
- In-line pressure switches (HP 2 off, LP 2 off). 4
- 5 Electronic pressure operated condenser fan speed controller (One Off)

CUS 40 - 60D

The following MCB's are fitted as standard:-

- Single phase control circuit breakers (mains and control voltage) 1
- 2 Three phase compressor circuit breakers

The following contactors/overloads are fitted:-

- CP1 to CP4 Main compressor contactors 1
- 2 Compressor thermal overloads
- 3 CD1 and CD2 - Condenser Fan Contactors

The following relays are fitted, some are option dependent:

- R1 and R3 Delay Start Relay Dual Compressor Circuit No 1 R4 and R6 Delay Start Relay Dual Compressor Circuit No 2 1
- 2
- R2 and R5 HP/LP Trip Relays 3

Other components are as follows, some are option dependent:

- **Compressor Sequence Switch**
- 2 T1 and T2 - Delay Start Timer - Dual Compressor - Circuit No 1
- 3 T4 and T5 - Delay Start Timer - Dual Compressor - Circuit No 2
- In-line pressure switches (HP 2 off, LP 2 off). 4
- 5 Electronic pressure operated condenser fan speed controller (Two Off)

Electrical Information

ELECTRICAL DATA

CUS		15D	20D	25D	30D	40D	50D	60D
Unit Data								
Nominal Run Amps (1)	А	30.4	35.6	47.2	53.0	62.8	82.9	97.5
Maximum Start Amps	А	115.7	140.2	202.3	205.0	149.5	164.8	220.5
Control Circuit	V				24VAC			
Mains Supply	V				400/3/50			
Permanent Supply	V				230/1/50			
Rec Mains Fuse	А	50	50	80	80	100	100	125
Rec. Permanent Fuse(2)	A	4	4	4	4	4	4	4
Max Incoming) Mains	mm²	25	25	35	35	50	50	95
Cable Size) Perm	mm²	2.5	2.5	2.5	2.5	2.5	2.5	2.5
Compressor								
Motor Rating	kW	6.9	8.9	11.6	13.4	8.9	8.9/13.4	13.4
Nominal Run Amps (1)	А	12.7	15.2	19.8	22.5	15.2	15.2/22.5	22.5
Locked Rotor Amps	А	98	120.0	175.0	175.0	120.0	120.0//175.0	175.0
Oil Sump Heater Rating	W	50	50	50	75	50	50/75	75
Type of Start				D	irect on Line)		
Condenser Fan								
Motor Rating	kW	0.55	0.55	0.55	0.55	0.55	0.55	0.55
Full Load	A	2.50	2.50	2.50	2.50	2.50	2.50	2.50
Locked Rotor Amps	А	5.80	5.80	5.80	5.80	5.80	5.80	5.80

(1) Nominal Run Amps based on 5°C evaporating and a 35°C ambient.

(2) CUS40-60 units do not require a separate permanent fused supply.

HCU		20D	25D	30D
Unit Data				
Nominal Run Amps (1)	А	38	46	56
Maximum Start Amps	А	127.4	157	207
Control Circuit	V		24VAC	
Mains Supply	V		400/3/50	
Permanent Supply	V		230/1/50	
Rec Mains Fuse	А	50	80	80
Rec. Permanent Fuse	А	4	4	4
Max Incoming) Mains	mm²	25	35	35
Cable Size) Perm	mm²	2.5	2.5	2.5
Compressor				
Motor Rating	kW	13.3	16.7	13.4
Nominal Run Amps (1)	А	14.9	19.2	24.2
Locked Rotor Amps	А	105	130	175.0
Oil Sump Heater Rating	W	18-38	18-38	75
Type of Start			Direct on Line	
Condenser Fan				
Motor Rating	kW	0.55	0.55	0.55
Full Load	A	2.50	2.50	2.50
Locked Rotor Amps	A	5.80	5.80	5.80

(1) Nominal Run Amps based on 5°C evaporating and a 35°C ambient.

Supply

Customer

Supply

Field Connections

С

HCU

CUS

		L1	0
		L2	0
		L3	0
		Ν	0
		Е	0
		L4	0
110 45 00		N1	0
05 15-30			
20-30 LINITS		500	0
20-30 014113		502	0
		530	0
		535	0
		531	0
		532	0
		526	0
		527	0
		11	0
		12	0
		13	0
	-	N	0
		E	0
		L4	0
		N1	0
		500	0
		502	0
		506	0
		513	0
40-60 UNITS		522	0
		552	0

→	Mains Incoming
	400/3/50

- ≯ L4-N1 Permanent Supply 230/1/50
- → 0V
- → 24VAC Customer's Control
- ➔ 502-530 Stage Two Cool Customer's Control
- ➔ 502-535 Stage One Cool Customer's Control Customer
- ➔ 531-500 Liquid Line Solenoid Circuit 2 ≯
 - 532-500 Liquid Line Solenoid Circuit 1
- 526-527 Common Volt Free Alarm N/O Contact →

→ Mains Incoming 400/3/50

- L4-N1 Permanent Supply ➔ 230/1/50
- 0V ->

0

0

0

0

0

0

0

0

→

523

555

507

514

507

514

522

523

526

527

- -24VAC - Customer's Control
- 502-506 Stage One Cool Customer's Control →
- ➔ 502-513 Stage Two Cool Customer's Control
- → 522-552 Stage Three Cool - Customer's Control
- → 523-555 Stage Four Cool - Customer's Control
- → 507-500 Liquid Line Solenoid 1 - Circuit 1
- ≯ 514-500 Liquid Line Solenoid 2 - Circuit 2
- →
- 507-500 Liquid Line Solenoid 1 Comp 1, Circuit 1 ≯ 514-500 Liquid Line Solenoid 2 - Comp 1, Circuit 2
- → 522-500 Liquid Line Solenoid 3 - Comp 2, Circuit 1

523-500 Liquid Line Solenoid 4 - Comp 2, Circuit 2

О ≯ 526-527 Common Volt Free Alarm N/O Contact 0

Commissioning Procedure – Example

CONDENSERS/CONDENSING UNITS - C/CUS/CUHS/HCU/CFCUS



Airedale International Air Conditioning Ltd Leeds Road, Rawdon, Leeds LS19 6JY ENGLAND Tel: 0113 239 1000 Fax: 0113 250 7219

TO BE COMPLETED IN CONJUNCTION WITH COMMISSIONING PROCEDURE RETURN WHITE COPY TO AIREDALE/RETAIN PINK COPY

Engineer:		Company:		Date:	
Mode	I: Serial No):	Sit	e Ref:	
1	Pre Commissioning Checklist				
1.1	Unit Condition Satisfactory	Comment:			
1.2	Holding charge retained	Circ 1	Yes/No	Circ 2	Yes/No
1.3	Electrical connections tight				V
1.4	Voltage at mains supply	L1-L2	V L2-L3	V L3-L1	V
1.5	System pressure test:				
Ι	Initial test pressure	Circ 1	Barg	Circ 2	Barg
ii	Final test pressure	Circ 1	Barg	Circ 2	Barg
iii	Test duration	Circ 1	Hrs	Circ 2	Hrs
2	Commissioning Checklist				
2.1	Final system vacuum	Circ 1	mBar	Circ 2	mBar
2.2	Vacuum hold time	Circ 1	Min	Circ 2	Min
2.3	Refrigerant type				
2.4	Refrigerant charge	Circ 1	kg	Circ 2	kg
2.5	Timer settings correct and operational	l (if fitted)			
	Low pressure override - 3mins	Circ 1	Mins	Circ 2	Mins
	Defrost - 30 mins	Circ 1	Mins	Circ 2	Mins
	Anti cycle timer -10 mins	Circ 1	Mins	Circ 2	Mins
2.6	Head pressure control set	Circ 1	Barg	Circ 2	Barg
2.7	HP/LP switch cut outs:	Circ 1	Barg	Circ 2	Barg
Ι	LP cut out - 2.0 barg	LP Cut Out	Barg	LP Cut Out	Barg
ii	LP cut in - 3.0 barg	LP Cut In	Barg	LP Cut In	Barg
iii	HP cut out - 27.0 barg	HP Cut Out	Barg	HP Cut Out	Barg
2.8	HGBP valve setting (if fitted)	Circ 1	Barg	Circ 2	Barg
2.9	Superheat at compressor	Circ 1	°C	Circ 2	°C
2.10	Added oil volume (if applicable)	Circ 1	Lt	Circ 2	Lt
2.11	Operating conditions:				
i	Suction pressure	Circ 1	Barg	Circ 2	Barg
ii	Discharge pressure	Circ 1	Barg	Circ 2	Barg
2.12	Compressor Amps (CU & CFCU)	L1	Amps	L1	Amps
		L2	Amps	L2	Amps
		L3	Amps	L3	Amps
2.13	Condenser Fan Amps	/	/ Amps	/ /	Amps
3	Other comments				

IMPORTANT: THIS IS AN IMPORTANT WARRANTY DOCUMENT AND WARRANTY COULD BE INVALIDATED SHOULD AIREDALE NOT HOLD A COPY ON FILE.

QTYENG 10 - 08/98

Commissioning Procedure

REFRIGERATION CIRCUIT -PRE-START CHECKS

Electrical	1	Check all electrical connections connections.	Check all electrical connections are tight, including contactor and all terminal onnections.		
	2	Check supply is available at the correct voltage and that any external fur circuit breakers are the correct rating.			
	3	Check that there is a proper ear	th connection to the condensing unit.		
	4	Check that there is a supply to the oil sump heater.			
IMPORTANT	Scrol phase direc	l compressors in range CU30 to 60D and HCU30D condensing units:- Check e rotation of electrical supply prior to running compressor as compressor is tion sensitive.			
Refrigeration	1	Check that there is a holding ch	arge of refrigerant in the system.		
	2	Check the high and low pressur follows:-	e switch settings. These should be as		
		HIGH PRESSURE SWITCH	27 Bar (400 psi) - CUT OUT		
		LOW PRESSURE SWITCH	0.5 Bar (7 psi) - CUT OUT		
			3.8 Bar (55 psi) - CUT IN		

REFRIGERATION CIRCUIT - CHARGING

Procedure The system should be charged in accordance with accepted good practice and the suction and discharge pressures should be constantly monitored whilst charging is in progress.

At the same time the compressor current should be monitored.

The system should be charged to the relevant suction and discharge pressures, together with the correct suction superheat (normally 5 $^{\circ}$ C to 6 $^{\circ}$ C).

Once this has been done, all the readings taken should be recorded on the commissioning sheets and a copy returned to Airedale for warranty purposes.

HEAD PRESSURE CONTROLLER ADJUSTMENT

CUS 15 - 30D AND HCU 20 - 30D

The head pressure is controlled by a single head pressure controller fitted with two pressure transducers - one to each circuit.

The fan speeds will increase if either head pressure goes above the preset level as the fans are common to both condenser coils.

Access to the controls for this head pressure controller is achieved by removal of the plastic cover which is secured by four screws.

Commissioning Procedure

HEAD PRESSURE CONTROLLER ADJUSTMENT	CUS 15 - 30D AND HCU 20 - 30D
Cut Off Mode	The voltage output to the fan is varied between 0-100% allowing head pressure control in ambients down to -20 °C. This is selected by turning the knob on the fan speed controller fully anti-clockwise. Cut off mode is standard operation for Airedale condensing units and factory set.
Minimum Speed Mode	The minimum voltage output to the fan can be varied between 45-95% of supply voltage by adjusting the knob within the minimum speed mode on the fan speed controller.
	Head pressure setting adjustment is achieved by altering the slotted dead screw on the pressure transducer.
	CUS 40 - 60D
	The head pressure can be controlled by the fan speed operation in one of two possible modes:
	The head pressure is controlled by a separate head pressure controller for each refrigeration circuit. The head pressure controllers are enclosed in a plastic box which contains all the necessary components including the pressure transducer. Connection to the respective refrigeration circuit is via a capillary of suitable length.
	There are Two control knobs in the controller.
	The upper knob is used to set the minimum speed for the fans. This can be adjusted to be between 50% and 90% of full speed. If the control is set to 0% then the minimum speed function is disabled and the fan will operate over the whole range of 0% to 100% dependent upon the head pressure. 0% is the standard setting for these controllers on Airedale condensing units.
	The lower knob is used to adjust the proportional band of the controller. This should be left at the factory setting.
	Adjustment of head pressure setpoint is by means of the slotted head adjuster on the pressure transducer head on the right-hand side of the controller.

Troubleshooting

GENERAL

FAULT	POSSIBLE CAUSE	REMEDY / ACTION
Compressor not operating.	No power to compressor	Check isolator, fuses, MCBs, contactor and control circuit wiring
	Low pressure switch operated (large or complete loss of refrigerant charge).	Recover refrigerant, repair, evacuate and recharge system.
	Compressor thermal protection device operated	Check if compressor overheated - possibly short of refrigerant
	Condenser fan thermal trip open circuit	Investigate and correct.
	Seized compressor, possibly due to lack of oil.	Replace compressor - investigate oil trapping and general installation.
	Defective compressor motor.	Check winding resistances - replace compressor. If burnt out follow burn out procedure using suction line burn-out drier.
Noisy Compressor.	Lack of oil.	Repair leaks if any, add oil if required but not too much - remember too much is as bad as too little. Investigate pipe system and trapping.
		Best method to pump down to see if oil can be encouraged back. If no oil still, drain compressor and measure in correct quantity.
	Expansion valve stuck in open position (abnormally cold suction line).	Ensure feeler bulb is tight on suction and superheat is correct (normally 5 °C to 6 °C.). Replace power assembly or valve as necessary.
	Worn or scored compressor bearing. (excessive knocking).	Replace compressor.
Head Pressure too high.	Condenser coil clogged or dirty.	Clean condenser.
	Air or other non-condensable gas in system.	Evacuate system and re-charge with new refrigerant.
	Overcharge of refrigerant.	Remove excess refrigerant from system by recovery system.

Troubleshooting REFRIGERATION

FAULT	POSSIBLE CAUSE	REMEDY / ACTION
Head pressure too high.	Condenser coil blocked or dirty	Clean condenser coil
	Head pressure controller faulty.	Check fan speed controller - if faulty - replace.
	Fan not operating or operating inefficiently.	Check motor - if faulty - replace.
Head pressure too low.	Fan operating too fast in low ambient conditions.	Check fan speed controller adjustment - if faulty - replace.
Compressor short cycles or LP cut-out operated.	LP switch set too high.	Adjust/replace as appropriate.
	Lack of refrigerant (bubbles in sight glass only as indication).	Check for leaks – reclaim refrigerant, repair, evacuate and recharge system.
	Clogged filter drier (pressure / temperature drop across it).	Replace once the cause has been identified and rectified.
	Condenser fan running at full speed in winter (full airflow).	Check fan speed controller setting - if faulty - replace.
Suction Pressure too low.	Low evaporator airflow (not Airedale Unit).	Check fan motors, belts and drives.
	Flash gas (bubbles in sight glass) at expansion valve.	Investigate for refrigerant leaks, repair and re-charge system.
	Clogged filter drier (pressure / temperature drop across it).	Replace.
	Obstruction in liquid line solenoid valve.	Pump down, inspect, clean or replace.
	Obstruction in expansion valve.	Pump down, inspect, clean or replace.

Troubleshooting REFRIGERATION

FAULT	POSSIBLE CAUSE	REMEDY / ACTION
Condenser fan not operating - power on.	Motor / fan assembly jammed	Isolate unit and check free rotation of motor / fan assembly. If faulty - replace.
	Fault at motor terminal box supply terminals	Isolate and check electrical connections are secure.
	Motor internal overheat protector tripped.	Carry out continuity check at terminals "TK" in motor terminal box. If tripped and motor hot - check bearings. If tripped and motor cold - replace motor.
	Power supply failure	Check power supply at circuit breaker.
	Wiring to motor	Check voltage at motor terminals.
	Faulty motor windings / capacitor	Motor humming would indicate fault in motor or capacitor.
	Minimum speed set too low.	Adjust head pressure controller to suit.
	Faulty pressure sensor.	Check electrical connections are secure at controller and pressure sensor. Replace controller and sensor (as they are matched sets).
	Faulty Controller.	Link wires "line" and "load" to bypass controller. If motor runs full speed - replace unit.
Condenser fan runs too fast.	High ambient condition or excessive re- circulation of air around condenser coil.	Check installation against design.
	Minimum speed setting incorrect.	Adjust as necessary.
	Incorrect pressure setting.	Adjust sensor screw as necessary.
	Faulty Controller.	Replace controller and sensor (as they are matched sets).
	Faulty pressure sensor.	Replace controller and sensor (as they are matched sets).
Condenser fans runs only slowly.	Incorrect pressure setting.	Adjust sensor screw as necessary.
	Faulty Controller.	Replace controller and sensor (as they are matched sets).
	Faulty Pressure sensor.	Replace controller and sensor (as they are matched sets).
	Motor wired incorrectly.	Check against wiring diagram - correct as required.
	Motor / capacitor faulty.	Replace.

Maintenance Rec SAFETY	WARNIN Out any	nents IG : Ensure that ALL power to the unit is switched OFF before carrying servicing or maintenance task.	
ACCESS	CUS 15	5 - 30D	
	Access to the compressors is via removable covers at the control panel end of the unit. The low covers allow access to the compressors whilst the upper doors allow access to the control panel.		
	Access is gained to the fan(s) from the top of the unit.		
	CUS 40) - 60D	
	Access panel. Ir dependi	to the compressors is via removable covers at the opposite end to the control n both cases there are removable covers which can be lifted off or hinged back ng upon their location.	
SERVICE CHECKS - THREE MONTHLY	At every	service visit the following checks should be carried out:-	
FAN AND MOTOR ASSEMBLY	1	Examine the fan and motor assemblies for lateral and end play in the bearings.	
	2	Examine the electrical gland plate to ensure that no water is entering the motor.	
	3	Examine the fan blades for damage and corrosion.	
REFRIGERATION CIRCUITS	1	Check the suction and discharge pressures using a service gauge manifold and compare them with the commissioning sheet. If there is any significant variation, then the fault should be found and corrected. Refer to the troubleshooting section.	
	2	Check that the high and low pressure switches are cutting out the compressors at the correct settings.	
		High pressure switch cut-out27.6 barLow pressure switch cut-out0.5 barLow pressure switch cut-in2.5 barLow pressure switch differential2.0 bar	
		Ensure that both switches stop the compressor.	
	3	Ensure the fan head pressure controller is controlling the head pressure at the required setting as shown on the commissioning sheets.	
	The gau caps on	iges can then removed from the system. Do not forget to replace the security the schraeder valves.	
CONDENSER COIL	Clean th long per hose or they hav	ne condenser coil with a stiff bristled hand brush. If dirt has accumulated over a riod, or tends to be greasy or sticky, then it may be necessary to use a water chemical pressure hose. Take care not to damage the fins and comb out if ve become damaged in any way.	
	IMPORT DAMAGE	ANT:- DO NOT USE STEAM FOR CLEANING CONDENSER COILS OTHERWISE E OR DANGER MAY RESULT FROM EXCESSIVE INTERNAL PRESSURES.	

Maintenance Requirements

CABINET	Wash down cabinet using a mild detergent. Treat any paint damage or rust as necessary.		
ELECTRICAL	1	Check all electrical connections for signs of overheating or arcing.	
	2	Check all cables for signs of chafing or physical damage.	
SERVICE CHECKS - YEARLY	As th 1	As three-monthly plus the following:- 1 Check all electrical connections for tightness.	
	2	Check all refrigeration connections with leak detector.	

Notes:





Head Office:

Airedale International Air Conditioning Ltd Leeds Road Rawdon Leeds LS19 6JY United Kingdom

Tel:	+44 (0) 113 239 1000
Fax:	+44 (0) 113 250 7219

e-mail: website: enquiries@airedale.com www.airedale.com

